

Buttercup Ave Storm Sewer Lining Bid Tab

DESCRIPTION	QUANT	UNIT	PROSHOT CONCRETE, INC		NATIONAL GUNITE	
			JNIT PRICE	TOTAL	UNIT PRICE	TOTAL
MOBILIZATION	1	Lump	\$10,000.00	\$10,000.00	\$1,500.00	\$1,500.00
REHABILITATE 42" CMP WITH AN INVERT LINER FROM 4:00 TO 8:00, USING 3 INCHES OF 5,000 PSI SHOTCRETE.	324	LF	\$80.00	\$25,920.00	\$151.50	\$49,086.00
FULL 360 DEGREE REPAIR AT EACH JOINT (THREE FOOT ON BOTH SIDES OF THE JOINT), AS NEEDED	15	EA	\$925.00	\$13,875.00	\$258.00	\$3,870.00
TOTAL				\$49,795.00		\$54,456.00